

ITEM 4.27.3 | CONTROLS AND OPERATING MECHANISMS - HEIGHT

The highest operable part of controls, dispensers, receptacles, and other operable equipment shall be placed within at least one of the reach ranges specified in 4.2.5 and 4.2.6. Electrical and communications system receptacles on walls shall be mounted no less than 15 in (380 mm) above the floor.

(“1991 Standards for Accessible Design”, 28 CFR 36 Appendix D)

